Work Order – Scope of Work

Job WX-2026-0147 · issued by [Local Weatherization Agency] – DCA subgrantee to [Weatherization Contractor LLC] – subcontractor to the agency · performance requirements from the energy audit (WPN 22-4)

SAMPLE DOCUMENT – Fictitious house and household. Test results, bills, prices and costs are illustrative values, not customer data. Prices follow an illustrative agency price list.

Job / client	WX-2026-0147 · Mrs. A. Example (fictitious)
Address	45 Sample Street, Hamilton Township, NJ 08610 (fictitious)
Scheduled	2026-12-01 to 2026-12-03
Contractor	[Weatherization Contractor LLC] – subcontractor to the agency · [NJ Home Improvement Contractor reg. no.] · [EPA RRP Firm cert. no.]
Crew lead	[Crew Lead Name], [BPI Infiltration & Duct Leakage / HEP Crew Leader]
Energy auditor (questions, change orders)	[Auditor Name] · [email]
Occupant	Occupant at home all day; bedroom AC window units used in July and August.

Test targets and stop-work conditions

Item	Before	Target / limit
Blower door	3,400 CFM50	≤ 2,300 CFM50 – if below 1,955 CFM50 call the auditor (ventilation rate is recalculated)
Worst-case CAZ depressurization	-3.8 Pa (FAIL)	≥ -3.0 Pa, tested at the end of every work day
Spillage, each natural-draft appliance at worst case	Gas furnace 25 s, Gas water heater 95 s (FAIL)	stops ≤ 60 s
Ambient CO	2 ppm	stop work and ventilate above 35 ppm

Stop work and call the auditor if: CAZ test fails after the day's work, a gas leak is found, suspected asbestos or vermiculite, knob-and-tube wiring, structural damage or moisture problems are uncovered, or the occupant asks to stop. No work outside this order without a signed change order.

Scope of work

A – Energy conservation measures (DOE WAP program operations)

ID	Measure / location	Specification	Line item	Qty	Unit	Unit price	Amount
AS-1	**Air sealing – attic bypasses and basement** Attic floor, basement sill and penetrations	Seal attic bypasses before insulating: top plates, plumbing stack and wiring penetrations, chimney chase (sheet metal and high-temperature sealant, maintain clearance to masonry), attic hatch weatherstrip. Basement: sill plate to foundation, utility penetrations. Guided by blower door; target listed under test targets. *SWS ch. 3 Air Sealing*	Air sealing labor	14	crew hr	$78.00	$1,092
			Materials: one-part foam, caulk, rigid board, high-temp sealant, sheet metal	1	lot	$210.00	$210
AI-1	**Attic insulation to R-49** Attic floor, 1,150 ft²	Blow cellulose over existing batts to R-49 total, uniform depth, depth rulers every 300 ft², certificate posted at hatch. Dam and insulate hatch, baffles at every soffit bay, keep 3 in. clearance to chimney and non-IC fixtures (dam). *SWS ch. 4 Insulation (attics)*	Blown cellulose, add R-40	1150	ft²	$1.25	$1,438

ID	Measure / location	Specification	Line item	Qty	Unit	Unit price	Amount
			Attic hatch dam and rigid foam on hatch *(IRM)*	1	ea	$95.00	$95
			Soffit baffles *(IRM)*	24	ea	$6.00	$144
WI-1	**Wall insulation – dense-pack cellulose** All exterior walls, 952 ft² net	Drill-and-fill from exterior through clapboard: remove one course, drill 2-9/16" holes into every cavity (above and below windows, check fire blocking), dense-pack cellulose at ≥ 3.5 lb/ft³, plug, reinstall siding. Verify fill with infrared scan or density check. Lead-safe work practices (see H&S). *SWS ch. 4 Insulation (walls)*	Dense-pack cellulose, drill and fill from exterior	952	ft²	$2.35	$2,237
			Replace split clapboards at drill line, prime *(IRM)*	1	lot	$120.00	$120
RJ-1	**Rim joist insulation and sealing** Basement rim/band joist, 142 ft perimeter	2 in. closed-cell spray foam (≈ R-13) on rim joist and sill, sealing sill-to-foundation joint. Install per manufacturer's evaluation report; thermal or ignition barrier as required by code. *SWS ch. 4 Insulation (rim joists)*	Closed-cell SPF, 2 in.	107	ft²	$4.20	$449
WH-1	**Low-flow showerhead 1.5 gpm** Bathroom	WaterSense showerhead 1.5 gpm; leave old showerhead with client only on request. *SWS ch. 7 Baseload*	Showerhead 1.5 gpm, installed	1	ea	$48.00	$48
WH-2	**Water heater pipe insulation** Basement, water heater	Insulate first 6 ft of hot and cold pipe at the water heater (keep 6 in. clearance from draft hood/flue); verify setpoint 120–125 °F. *SWS ch. 7 Baseload*	Pipe insulation, 12 ft, installed	1	lot	$45.00	$45
LT-1	**LED lamps** Living room, kitchen, hall/bath, basement	Replace remaining incandescent and CFL lamps with ENERGY STAR LED of equal lumen output. *SWS ch. 7 Baseload*	LED lamps	11	ea	$4.50	$50
			Installation	0.5	hr	$78.00	$39
RF-1	**Refrigerator replacement (metered)** Kitchen	ENERGY STAR top-freezer, 18 cu ft, label ≤ 385 kWh/yr; haul away old unit to a certified recycler (refrigerant recovery), keep disposal receipt in client file. *SWS ch. 7 Baseload*	ENERGY STAR refrigerator 18 cu ft, delivered	1	ea	$899.00	$899
			Removal and recycling of old unit	1	ea	$85.00	$85
	Subtotal						**$6,951**

B – Health & safety (separate H&S budget)

ID	Measure / location	Specification	Line item	Qty	Unit	Unit price	Amount
HS-1	**Gas leak at furnace gas cock union**	HVAC technician to remake union, leak-test all furnace connections with CGD and soap solution; occupant informed in writing *SWS ch. 2 Health & Safety*	Gas leak repair and re-test	1	ea	$95.00	$95
HS-2	**Dryer exhaust duct**	Install rigid metal duct, foil tape (no screws), exterior hood with damper; clean lint *SWS ch. 6 Ventilation*	Dryer vent, rigid metal, exterior hood	1	ea	$165.00	$165
HS-3	**ASHRAE 62.2 ventilation – bath exhaust fan**	Install the fan described under ventilation, duct to exterior (insulated duct in attic, roof or gable cap with damper), measure flow at both speeds *SWS ch. 6 Ventilation*	Bath fan with continuous/boost controls, ducting, wiring	1	ea	$585.00	$585
HS-4	**Smoke and CO alarms**	Install combination smoke/CO alarm in the hallway outside bedrooms and a CO alarm in the basement; explain operation *SWS ch. 2 Health & Safety*	Combination smoke/CO alarm, 10-yr sealed battery	1	ea	$62.00	$62

SAMPLE

ID	Measure / location	Specification	Line item	Qty	Unit	Unit price	Amount
			CO alarm, basement	1	ea	$48.00	$48
HS-5	**Radon precautions**	Airtight sump pit cover with sealed penetrations, seal slab cracks and floor penetrations *SWS ch. 2 Health & Safety*	Airtight sump cover, sealing of floor penetrations	1	ea	$140.00	$140
HS-6	**Lead-safe work practices**	EPA RRP lead-safe practices for drilling siding and any interior disturbance: containment, HEPA cleanup, cleaning verification, records *SWS ch. 2 Health & Safety*	RRP setup, containment and cleaning verification	1	lot	$180.00	$180
DS-1	**Duct sealing – supply and return in basement** Basement: furnace cabinet, plenums, takeoffs, panned returns	Seal return plenum, filter slot (cover), cabinet seams and panned joist returns with mastic and fabric; seal supply plenum and takeoffs. Re-test CAZ worst case with air handler on. *SWS ch. 5 HVAC (duct sealing)*	Duct sealing labor	6	crew hr	$78.00	$468
			Mastic, mesh, filter slot cover	1	lot	$60.00	$60
	Subtotal						**$1,803**

Work order total	Amount
A – Energy conservation measures	$6,951
B – Health & safety	$1,803
Total work order	**$8,754**

SWS = DOE/NREL Standard Work Specifications as adopted in the state field guide. Measures evaluated in the audit but not cost-effective are not part of this order: HF-1 Furnace replacement – 95 % AFUE sealed combustion.

Materials (estimate)

ID	Measure	Quantity
AI-1	Attic insulation to R-49	10.8 in. settled depth added (R-40 at R-3.7/in.), 1.6 lb/ft³ → 1,658 lb ≈ 67 bags of 25 lb
WI-1	Wall insulation – dense-pack cellulose	cavity volume 236 ft³ at 3.5 lb/ft³ (+10% waste) → 909 lb ≈ 37 bags of 25 lb
RJ-1	Rim joist insulation and sealing	107 ft² × 2 in. = 214 board feet closed-cell SPF

Check coverage against the manufacturer's bag label (R-value, thickness and coverage per bag) and post the attic insulation certificate at the hatch.

Daily combustion safety log

Date	Work done	Worst-case CAZ Pa	Spillage WH s	Spillage furnace s	Ambient CO ppm	Pass	Initials
_____	_____	_____	_____	_____	_____	☐	_____
_____	_____	_____	_____	_____	_____	☐	_____
_____	_____	_____	_____	_____	_____	☐	_____
_____	_____	_____	_____	_____	_____	☐	_____

Documentation to return with the invoice

Document	Attached
Before/after photos of every measure (attic depth rulers, hatch dam, baffles, wall plugs, rim joist, duct seams, fan, alarms)	☐
Attic insulation certificate, cellulose bag count and wall density check	☐
Final blower door reading and daily CAZ log (above)	☐
Fan flow measurement of the bath fan at continuous and boost speed	☐
EPA RRP records: certified renovator, containment, cleaning verification	☐
Refrigerator recycling receipt, product data of installed equipment	☐
Signed change orders (if any)	☐

SAMPLE

Change orders

No.	Description / reason	Amount	Auditor approval	Date
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____

Issued – energy auditor / agency
signature / date

Accepted – contractor crew lead
signature / date

Work completed – contractor
signature / date

SAMPLE